

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-097-00004-0000

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Gulf Oil Corporation, c/o M. F. Barnes

Complete Address: Box 877, Great Bend, Kansas

Lease Name Pyle-Herring Well No. # 1

Location NW NW NE Sec. 15 Twp. 28 Rge. 16 (E) (W) W

County Kiowa Total Depth 4820'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 12:30PM Day 9th Month Oct. Year 1965

The Above well was plugged as follows:

396' of 9 5/8" surface pipe, cement circulated. 4819' of 5 1/2" long string,
cemented with 100 sacks. Top perferation 4680'. Bottom plug was pushed to
4675', and 50' of sand bridge, and cemented with 5 sacks. 4105' of 5 1/2"
long string was recovered from the hole. Fluid was up in the hole. Bridge
plug was pushed in fluid to 300', rock bridge from 300' to 290'. 4 sacks of
cement was mixed in barrel, and put in plug at 290', through the dump bailer,
and let set over-night. Next morning hole was bailed dry, and 24 sacks of
cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 12 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Ebling
Well Plugging Supervisor

INVOICED

DATE 10/11/65
INV. NO. 1960-4