

*4*  
KANSAS  
STATE CORPORATION COMMISSION

15-097-10150-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 22, 1968.

Operator's Full Name Western Oil Field Service

Complete Address: Box 163, Great Bend, Kansas 67530

Lease Name Binford "A" Well No. # 1

Location C NE NW Sec. 4 Twp. 28 Rge. 16 (E) (W)W

County Kiowa Total Depth 4707'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:30AM Day 26th Month January Year 1968

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated, 4667' of 4 1/2" long string,  
cemented with 150 sacks. Top perferation 4650'. Bottom of the hole was  
sanded to 4600', and cemented with 4 sacks, through the dump bailer, with  
cement from 4600' to 4550'. 2956' of 4 1/2" long string was recovered from the  
hole. Fluid level in the hole was at 250', bridge plug and rock bridge from  
250' to 240', and cemented with 25 sacks, with cement from 240' to 165'.  
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented  
with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 1/29/68  
INV. NO. 9168-U