

15-097-30094-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Woods Petroleum Corporation

Complete Address: Box 18667, Oklahoma City, Oklahoma

Lease Name E. M. Pyle Well No. # 1

Location NW SE Sec. 1 Twp. 28 Rge. 19 (E) (W) W

County Kiowa Total Depth 4971'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: This well is to be used for a disposal well

Plugging Contractor: _____

Address: _____ License No. _____

Operation Completed: Hour _____ Day _____ Month _____ Year _____

The Above well was plugged as follows:

408' of 8 5/8" surface pipe, cemented with 200 sacks. All perforations were squeezed with 27 sacks of cement. When this well was drilled there was a lost circulation area from 530' to 600', this is the intended disposal area. 725' of 4 1/2" casing was run in the hole. Hole was full of heavy drilling mud, static level was at 20', 4 1/2" casing had to be circulated through this heavy mud. A Halliburton float collar was run on the bottom of the 4 1/2" casing. 200 sacks of cement was pumped into the 4 1/2" casing at 725', bringing the top of the cement to 500', in the lost circulation area. 1" pipe was run to 500', and cemented with 300 sacks, bringing the top of the cement to 430'. 1" pipe was run to 430', and cemented with 100 sacks to the base of the cellar. This cementing was done by Halliburton

I hereby certify that the above well was plugged as herein stated. Cementing Company

Completed at 10:30 A.M. July 11, 1966
3900' of 4 1/2" long string had been recovered from the hole

Signed: Archie Elving
Well Plugging Supervisor