

14  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
Rev. 6-26-62  
15-097-10/66-0000

RECEIVED  
STATE CORPORATION COMMISSION

NOV 8 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name J. Mark Richardson & Earl S. McCandless  
Complete Address: 502 Union Center Bldg., Wichita, Kansas  
Lease Name Seacat Well No. # 1  
Location C SE NE Sec. 23 Twp. 28 Rge. 19 (E) W  
County Kiowa Total Depth 4946'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: Gabbert-Jones, Inc.  
Address: 514 Orpheum Bldg., Wichita, Kansas License No.       
Operation Completed: Hour 9:00 PM Day 6th Month Nov. Year 1965

The Above well was plugged as follows:

310' of 8 5/8" surface pipe, cement circulated with 235 sacks. Hole  
was filled with drilling mud to 275', 1st cementing plug, bridged  
solid with dry cement and hulls on fluid at 275', and cemented with  
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged solid with dry cement and hulls on fluid at 40', and cemented  
with 10 sacks to the base of the cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Ebering  
Well Plugging Supervisor

DATE

11/8/65

INV. NO.

2124-W