

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
6-25-1979  
JUN 25 1979

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
API Number 15-097-26443-0000 (of this well)

Operator's Full Name Cherokee Resources, Inc.

Complete Address 432 Mayo Bldg., Tulsa, Okla. 74103

Lease Name Parmar Well No. 1-A

Location C W/2 SW Sec. 17 Twp. 28S Rge. 19 (E)      (W) X

County Kiowa Total Depth 4930

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683


Operation Completed: Hour 4:15 Pm. Day 21 Month 6 Year 1979

The above well was plugged as follows:

488'-8 5/8" casing w/300 sax cement. 4 1/2" casing set at 4921' w/125  
sax cement. 9' open hole- Sand back to 4900'- Top sand w/4 sax mixed  
cement w/ dump bailer. Pull 3600' 4 1/2" casing- Allied mixed & pumped  
5 sax hulls-25 sax gel-Release plug-Mixed & pumped 135 sax 50/50 posmix  
cement w/ 4% gel & 3% cc to top of casing. Shut in w/200# pressure.

I hereby certify that the above well was plugged as herein stated:

**INVOICED**

Signed:   
Well Plugging Supervisor

DATE 6-26-79

INV. NO. 9887-W