

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,676-0600

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name F. G. F. Petroleum

Complete Address 209 E William, Wichita Kansas 67202

Lease Name Bancum Well No. 1

Location C-NE NW Sec. 12 Twp. 28S Rge. 17W (East) (West)

County Kiowa Total Depth 5100

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address _____ License No. 683

Operation Completed: Hour: 11:00AM Day: 21 Month: September Year: 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

RECEIVED 81
SEP 24 1981
CONSERVATION DIVISION
Wichita, Kansas

There is 640' of 8 5/8" surface casing cement circulate with 340 lbs of cement. There is 4452' of 5 1/2" production pipe cemented in hole 150 lbs of cement were used. Perforations were from 4404' to 4408' & 4278' to 4282'. The top of cement on out side of production pipe was 3800'. 1st plug sand bottom & pumped 5 lbs of cement on bottom. 2nd plug released rubber plug at 600' pumped 4 lbs of bull & 10 lbs of Jell & 50 lbs of cement on top of rubber plug. 3rd plug at 350' with 7 lbs Jell & 35 lbs of cement. 4th plug 40' to 0' with 8 lbs Jell & 15 lbs cement. Plugging accomplished by Habalurta Cementing out of Pratt Co.

I hereby certify that the above well was plugged as herein stated.

DATE 10/16/81

Signed: Paul Justice
Conservation Division Agent

INV. NO. 9827-W