

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

6-10-1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. B. Y. Newman of J. E. Newman has this  
date requested permission to plug the following described well:

Mr. Newman guarantees payment of the plugging fee.

Operator's full Name: J. E. Newman

Complete Address: 2005 Tower Bldg., Denver, Colorado

Lease Name: Rezeau Well No. # 1

Location: NW NW SW Sec. 12 Twp. 28 Rge. 15 (E) (W) W

County Pratt Total Depth 4799 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Newman was instructed to plug the well as follows:

268' of 8 5/8" surface pipe, cement circulated. 4550' of  
2 1/2" tubing for long string, cemented with 100 sacks. top  
perferation 4476'. Hole was squeezed to 3730', with 35  
sacks cement. Fill hole with mud to 240', 10' rock bridge,  
cement with 20 sacks. Fill hole with mud to 40', 10' rock  
Bridge, cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving  
Conservation Division Agent