

State of Kansas



15-159-20814-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

May 12, 1979

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. C. Ray Rice of Sterling Drilling Co. has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Howell Oil Company

Complete Address: P.O. Box 2091 Washington Center, Hutchinson, Kansas

Lease Name: Blackhall Well No. 1

Location: 75' N. of SW SE SE Sec. 5 Twp. 21 Rge. 8 (E) (W) X

County: Rice Total Depth 3444' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Rice was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through  
drill pipe at 500'. Pump 25 sacks cement through  
drill pipe at 210'. Push plug and 1/2 sack hulls  
to 40' and cement hole to base of cellar with 10 sacks.  
Bridge rat hole and cement with 2 sacks

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

MAY 17 1979  
05-17-79  
CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
Conservation Division Agent