



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

July 11, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1970

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock,  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 800-200 W. Douglas, Wichita, Kansas 67202

Lease Name: Timbers Well No. 1

Location: App. NW NE NE Sec. 8 Twp. 21 Rge. 8 (X) (W) X

County: Rice Total Depth 3623' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Push 5 1/2" plug to 3310'. Fill hole with sand to 3300' and cement with 5 sacks cement. Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent