

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 4 1967

CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Intent to Drill,  
 filed August 16, 1967.

Dear Sir:

Mr. H. G. Pankratz of H-30 Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: Wrico Drilling Company

Complete Address: 6631 East Kellogg, Wichita, Kansas

Lease Name: Pagett Well No. # 1

Location: SE NE SW Sec. 20 Twp. 27 Rge. 5 (E)(W) W

County Kingman Total Depth 3835' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

209' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill  
hole with drilling mud to 200', alt cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving  
 Conservation Division Agent