



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1965

CONSERVATION DIVISION
Wichita, Kansas

6-14-1965

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Courange of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Courange guarantees payment of the plugging fee.

Operator's full Name: Wm. Gruenerwald & Associates, Inc.

Complete Address: Box 909, Colorado Springs, Colorado

Lease Name: J. W. Price Well No. # 1

Location: C SE SE Sec. 4 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5050' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Courange was instructed to plug the well as follows:

499' of 8 5/8" surface pipe, cement circulated with 400 sacks.
Fill hole with drilling mud to 280', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent