



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

9-January 1982

15-057-20182-0000

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Albert Hnush of Kelso Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: Pickrell Drilling Co.

Complete Address: Litwin Bldg, Suite 205 Wichita, Kansas 67202

Lease Name: Hicks Well No. A 2

Location: C-5 1/2-N 1/2 Sec. 11 Twp 28 S Rge. 21 W (E) (W)

County: Ford Total Depth: 5105

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: This well was completed but never produced

Mr. Hnush was instructed to plug the well as follows:

There is 611' of 8 1/8" surface casing cement circulated with 275 bbls of cement. They ran 5090' of 4 1/2" production pipe cemented it with 150 bbls of cement with cement up outside of pipe to 4410'. They plugged back to 4965'. The perforations from 4953' to 62'. 1st plug sand bottom back to 4900' put 4 bbls of cement on top of sand, 2nd plug 5 bbls hulls 17 bbls gel, 50 bbls of cement, 8 bbls gel, then release rubber plug.

Very truly yours,

RECEIVED  
STATE CORPORATION COMMISSION

Paul Luttich  
Conservation Division Agent

JAN 19 1982

CONSERVATION DIVISION  
Wichita, Kansas

(over.)

1-19-1982

and pumped 100 lbs of cement out of it. The  
Cement used was 50/50 price with 4% J.L. & 3% C.C.  
They had recovered 4020' of 4 1/2" production pipe.

The plugging was accomplished by Allied  
Cementing.