

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1965

CONSERVATION DIVISION  
Wichita, Kansas

8-30-1965

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Joe Butts of Mull Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Butts guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Ralstin Well No. # 1

Location: C SW NE Sec. 36 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5038' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Butts was instructed to plug the well as follows:

628' of 8 5/8" surface pipe, cement circulated with 325 sacks.  
Fill hole with drilling mud to 300', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

*Archie Elving*