

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 19 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

2-19-1963

Dear Sir:

Mr. Dean McLemore of Jones and Gebert Oil Co. has this

date requested permission to plug the following described well:

Mr. McLemore guarantees payment of the plugging fee.

Operator's full Name: Jones and Gebert Oil Co.

Complete Address: 1007 Central Bldg., Wichita 2, Kansas

Lease Name: Sidener Well No. # 1

Location: C NE SE Sec. 30 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5185 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. McLemore was instructed to plug the well as follows:

405' of 8 5/8" surface pipe circulated with cement.

Fill hole with heavy mud to 180', 1/2 sack hulls, 1st cementing plug, cement with 20 sacks. Fill hole with heavy mud to

40', 1/2 sack hulls, 2nd cementing plug, cement with 10 sacks

to base cellar. Rat and mouse ~~bricked~~ hole bridged and cemented with 4 sacks.

Very truly yours,

Annie Elving  
 Conservation Division Agent