



15-097-01013-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

1-21-1966

Dear Sir:

Mr. Dwight Defenbach of Rains & Williamson Oil Co has this date requested permission to plug the following described well:

Mr. Defenbach guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson, Mull Drilling & Sam Wallingford

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Solan Well No. # 1

Location: C SE SE Sec. 27 Twp. 28 Rge. 20 (E)(W) W

County Kiowa Total Depth 5055' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Defenbach was instructed to plug the well as follows:

388' of 8 5/8" surface pipe, cemented with 250 sacks. Fill hole with drilling mud to 380', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent