

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-057-20,481-0000

LEASE NAME Hayse

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-24

3870 Ft. from S Section Line

1320 Ft. from E Section Line

LEASE OPERATOR Zinke & Trumbo, LTD.

SEC. 24 TWP. 28S RGE. 21 ~~W~~(W)

ADDRESS 1202 E. 33rd St., Suite 100, Tulsa, OK 74105

COUNTY Ford

PHONE#(918) 743-5096 OPERATORS LICENSE NO. 30034

Date Well Completed 02-21-90

Character of Well D&A

Plugging Commenced 02-21-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 02-21-90

The plugging proposal was approved on 02-21-90 (date)

by State plugging, Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8"	107'	None
				8 5/8"	667'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Circulate heavy mud in hole. 1st plug from 5700' to 5540' w/40 sx. 2nd plug from 1350' to 1150' w/50 sx. Rathole-15 sx. Mousehole-10 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinke & Trumbo, LTD.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 1990
Wichita, Kansas

Sharan J. Branstetter
Notary Public
My Commission Expires: May 18, 1993

