

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-057-10005-0000
Drilled 1956

LEASE NAME Karns

WELL NUMBER 1

NE SW NE Ft. from S Section Line

Ft. from E Section Line

SEC. 23 TWP. 28SRGE. 21 KBXor(W)

COUNTY Ford

Date Well Completed 11-28-56

Plugging Commenced 10/4/91

Plugging Completed 10/9/91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graham Michaelis Corporation

ADDRESS P.O. Box 247, Wichita, KS 67201

PHONE/(316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Gas

(Oil, Gas, DH, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filled? X If not, is well log attached? X

Producing Formation X Depth to Top _____ Bottom _____ T.O. 5100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASINO RECORD RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	244	200 sx none
				5 1/2	5099	2500

OCT 23 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
300 hulls, 15 jell, 50 cement, 10 jell, 100 hull, 8 5/8" wiper plug, 175 sacks cement, pump in surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Jeff Sletto (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jeff Sletto

(Address) Medicine Lodge

State of Kansas - Notary Public
GLEND MORRISON
 My Appt. Exp. 5-17-94

SUBSCRIBED AND SWORN TO before me this 11 day of October, 19 91

Glenda Morrison
 Notary Public

My Commission Expires: 5-17-94

Pumped 15 sx cement in 4" water well csg to fill from top to bottom.

OCT 17 1991

R

GRAHAM- MICHAELIS DRILLING COMPANY

WILLIAM L. GRAHAM

W. A. MICHAELIS, JR.

HOBERT 4-8394

15-057-10005-0000

On 7-24-56

GRAHAM BUILDING • 211 NORTH BROADWAY • WICHITA 2, KANSAS

DRILLING-IN REPORT

KARNS No. 1

LOCATION: NE SW NE Sec. 23-28^{21W}SHW
Ford County, Kansas

CASING RECORD: 8 5/8" @ 244' w/200 sacks cement.
5 1/2" @ 5099' w/200 sacks cement.

ROTARY T.D.: 5100'

ELEVATION: 2369' K.B.

TOPS:	Heeb	4180'
	Toro	4200'
	Douglas	4280'
	Br. Im.	4333'
	Lans	4342'
	B/KC	4652'
	Miss	5004'

11-23-56 - Moved in cable tools and rigged up.

11-24-56 - Logged hole and perforated 5040-5060', made 6,100,000 CFG, natural.
Acidized with 500 gal. mud acid.

11-25-56 - Finished on 805# pressure. Swabbed hole down - making 13,000,000 CFG,
on 4 hr. blow down, 1600# shut in pressure. Acidized with 6,000 gal.
max. pressure 400#, finished on 300#, vac when pump shut down.
Run tubing.

11-26-56 - Swabbed hole down. Making 5,604,000 CFG, still wet.

11-27-56 - Making 14,000,000 CFG.

11-28-56 - Layed down tools.

Completed by Charlie Starks

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1991

COMP. NO. 1005