

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-057-26191-0060

LEASE NAME Mann

WELL NUMBER B-2

SPOT LOCATION _____

SEC. 14 TWP. 28 SRGE. 21 (X) or (W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 1-23-86

Plugging Completed 1-27-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 200 West Douglas Suite #300 Wichita, Ks. 67202

PHONE # (316) 265-9441 OPERATORS LICENSE NO. 5191

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom P.B.T.D. 5132'
Perfs 5044-5050'.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	625'	8 5/8		0
		625	516 1/2	2 7/8		0
				1 1/2		153 jts.
				5/8		203 rods

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Filled 140 jts. of casing with sand, top of sand 4992'
1-29-86 Pumped 10 sx. cement, perf. at 700'. pumped 250 sx. of 50/50 poz, 2% gel
down 2 7/8 casing, ran measuring line, found fluid at 250'. Top of cement 700'. Mixed
190 sx. 50/50 poz 2% gel, filled casing and 2 7/8 to surface.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893
Address Box 847 Pratt, Ks. 67124

STATE OF Kansas COUNTY OF Pratt ss.

Judy Berry (employee of plugging contractor) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 13 day of Feb., 1986

Dorothy M. Fugason
Notary Public
STATE CORPORATION COMMISSION

My Commission expires: Feb. 16, 1989

FEB 14 1986 2-14-1986

Form CP-4
Revised 01-84

REGISTRATION DIVISION

KANSAS

Geo. Survey request samples on this well.

WEL' COMPLETION REPORT AND DRILLER'S LOG

s. 14 T. 28 R. 21 W

API No. 15 - 057 - 20 101-0000

C E2 NW SW

Operator

Texas Oil & Gas Corp.


PROD. FILE

County Ford

640 Acres

Address

200 West Douglas, Suite 300 Wichita, Kansas 67202



Well No.

#2

Lease Name

Mann "B"

Footage Location

1980' feet from XX (S) line 2310' feet from (X) (W) line.

Principal Contractor

Slawson, Rig #6

Geologist

Professional Well Logging

Spud Date

1-16-81

Date Completed

2-16-81

Total Depth

5165

P.B.T.D.

5132

Directional Deviation

Not directionally drilled

Oil and/or Gas Purchaser

Delhi

Elev.: Gr. 2367

DF KB 2373

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor		16"		110'			
Surface		8-5/8"		625'		475	
Production		2-7/8"		5164'		200	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPE (13 h.)	Miss.	5044-50'

TUBING RECORD

Size	Setting depth	Packer set at
1 1/2"	5041	5020

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/500 gals 15% nEA @ 1 BPM.	5044-50'
Killed well w/81 bbls 2% KCl water	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
4-14-81	flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil N/A	Gas 700 MCFD	Water none	Gas-oil ratio N/A
Disposition of gas (vented, used on lease or sold)	Sold	Producing interval (s)	5044-50'	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

FIELD: PLEASANT VALLEY