

15-057-10002-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ford County, Sec. 11 Twp. 28 Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines 1250' S of NL & 330' E of WL of

Lease Owner W. J. Goppinger, et al SE/4

Lease Name Kirkpatrick Well No. 1

Office Address 507 Union National Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 9-7-54 19

Application for plugging filed 5-3-57 19

Application for plugging approved 5-6-57 19

Plugging commenced 6-25-57 19

Plugging completed 7-4-57 19

Reason for abandonment of well or producing formation Well became uneconomical to Operate

If a producing well is abandoned, date of last production June 24 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas

Producing formation Mississippian Depth to top 4986' Bottom 5014' Total Depth of Well 5060 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	325'	none
				5 1/2	5059.	3500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom and filled up with sand from 5020' to 4975', dumped 5 sacks of cement on top of sand, Filled with mud to 315'.

Set a rock bridge at 315' and dumped 20 sacks of cement on rock bridge. Filled up with mud to 35'. Set a rock bridge at 35' and dumped 10 sacks of cement on bridge which filled up to base of cellar.

RECEIVED  
JUL 12 1957  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor R. & D Casing Pulling Company  
Address Ellinwood, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Lee Foulson (employee of owner ~~XXXXXXXXXXXX~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lee Foulson  
507 Union National Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 1957

My commission expires March 7, 1960  
Mayree Broadus Notary Public.

PLUGGING  
FILE SEC 11 T. 28 R. 21W  
BOOK PAGE 10 LINE 40

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY

15-057-16002-0000

Company W. J. COPPINGER.  
Farm Kirkpatrick No. 1

SEC. 11 T. 28 R. 21W  
C S/2 SW NW SE  
1250' S of NL, 330' E of WL SE

Total Depth. 5060  
Comm. 8-13-54 Comp. 9-7-54  
Shot or Treated.  
Contractor. W. J. Coppinger  
Issued 1-1-55

County Ford

KANSAS



Elevation. 2351 DF

Production. 3,800,000 Gas

CASING:

8 5/8 @ 325' w/ 200 sx cmt.  
5 1/2 @ 5059' w/ 100 sx cmt.

Figures Indicate Bottom of Formations

surface clay	75
sand	105
shale	320
red bed & shale	520
sand	610
red bed	910
shale, shells & red bed	1335
anhydrite	1370
shale & red bed	1385
red bed & shells	1775
shale & shells	1890
anhydrite	1920
shale	1970
shale, red bed & shells	2145
shale & shells	2400
lime & shale	2565
lime	2745
lime & shale	3835
lime	4485
lime & chert.	4520
lime & shale	4580
lime	5060
Total Depth	

TOPS:	
Anhydrite	1355
Heebner	4145
Lansing	4304
Mississippi	4960

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING	
FILE SEC	11 T. 28 R. 21W
BOOK PAGE	10 LINE 40