

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-057-20,346

LEASE NAME Harsha

WELL NUMBER "C" #1

SPOT LOCATION 150W SW NW

SEC 1 TWP. 28 RGE. 21 (E) or (W)

COUNTY Ford

Date Well Completed _____

Plugging Commenced 10-16-84

Plugging Completed 10-27-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company

ADDRESS Box 1303, Great Bend, Ks. 67530

PHONE # (316-793-6010) OPERATORS LICENSE NO. 5123

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 1

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom T.D. 5100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	583'	None
				4-1/2"	5090'	4,146.11'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 4935' and 4 sacks of cement. Shot casing at 4400' & 4100'. Pulled 105 joints of 4-1/2" casing. Squeezed well with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 300 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1984

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman
Notary Public