

15-097-30031-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa County. Sec. 36 Twp. 28S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW NE

Lease Owner Mull Drilling Company, Inc.

Lease Name Ralstin Well No. 1

Office Address 1625 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed August 22 19 65

Application for plugging filed August 22 19 65

Application for plugging approved August 22 19 65


Plugging commenced August 22 19 65

Plugging completed August 22 19 65

Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes---- Archie V. Elving



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 50.38 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	650	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 300', 2 sx dry cement,
1/2 sx hulls. 23 sx cement,
mud to 40'. 1 sx dry cement,
1/3 sx hulls. 9 sx cement to
surface. 2 sx cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1965

CONSERVATION DIVISION
Wichita, Kansas

8-27-1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling

Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

George A. Angle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle

1720 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 25th day of August, 19 65

My commission expires 5-22-66

Jean D. Hollan
Notary Public.

DRILLERS LOG

15-097-30031-0000

Ralstin No. 1

CASING RECORD: 8 5/8" @ 650' w/300 ex cement
 COMPANY: Mull Drilling Co., Inc.
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: August 10, 1965
 COMPLETED: August 22, 1965
 TOTAL DEPTH: 5038

DESCRIPTION: C SW NE 36-28S-20W
 Kiowa Co., Kansas
 ELEVATION: 2343 DF
 2346 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil & Clay	0	74	
Sand & Shells	74	190	
Shale Streaks of Sand	190	441	
Sand	441	465	
Shale & Shells	465	642	
Anhydrite	642	650	
Blane Anhydrite	650	659	
Shale & Shells & Redbed	659	850	
Shale & Redbed	850	1290	
Anhydrite	1290	1303	
Shale & Shells	1303	2392	
Lime & Shale	2392	2585	
Lime	2585	2800	
Lime & Shale	2800	3960	
Lime	3960	4875	
Cherty Lime & Shale	4875	4916	
Lime & Shale	4916	5005	
Mississippi	5005	5038	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 27 1965
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 25th day of August, 1965.

David Halliday
 Notary Public

