

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21,290-0000

LEASE NAME Joyce

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-30

1020 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 30 TWP. 28 RGE. 20 (E) or (W)

LEASE OPERATOR Halliburton Oil Producing Co.

COUNTY Kiowa

ADDRESS 525 Central Park Dr. #1-210 Oklahoma City, OK 73105

PHONE# (405) 525-3371 OPERATORS LICENSE NO. 5988

Date Well Completed 7-15-90

Character of Well D&A

Plugging Commenced 7-15-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-15-90

The plugging proposal was approved on 7-11-90 (date)

by Dick Kapp (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 5200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE OF KANSAS

Formation	Content	From	To	Size	Put In	Pulled out
						<u>JUL 23 1990</u>
						CONSERVATION DIVISION Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 1300' w/50 sacks cement thru drill pipe

Next Plug: @ 650' w/50 " " " " "

Top Plug: @ 40' w/10 " " " " "

10 sacks cement in Mouse Hole 15 sacks in Rat Hole 10 sacks in water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Halliburton Oil Producing Co.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530



Subscribed and sworn to before me this 19 day of July, 19 90

Dorothy M Hague
Notary Public

My Commission Expires: 5-29-94

15-097-21290-0000

DRILLER'S WELL LOG

DATE COMMENCED: July 4, 1990
DATE COMPLETED: July 15, 1990

Halliburton Oil Producing Co.
JOYCE #1-30
300' S of C SW
Sec. 30, T28S, R20W
Kiowa County, Ks.

- 0 - 80' Surface Soil, Clay, sand
- 80 - 350' Clay
- 350 - 515' Red Bed
- 515 - 3010' Shale & Lime
- 3010 - 4305' Lime & Shale
- 4305 - 5200' Lime
- 5200' RTD

ELEVATION: 2329' K.B.

Surface pipe: Set used
8-5/8", 20# pipe @ 532'
w/350 sacks 60/40pozmix
2%gel 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

REC'D
STATE

JUL 23 1990

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

CONSERVATION DIVISION
Wichita, Kansas

Ervin Neighbors

Subscribed and sworn to before me this 19 day of July 1990.

Dorothy M. Hague
Notary Public

