


15-097-01013-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Kiowa County. Sec 27 Twp. 28S Rge. (E) 20 (W)  
Location as "NE/CNW/SW" or footage from lines C SE SE  
Lease Owner Rains & Williamson Oil Co.  
Lease Name SLOAN Well No. 1  
Office Address 1425 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 17 1966  
Application for plugging filed January 17 1966  
Application for plugging approved January 17 1966  
Plugging commenced January 17 1966  
Plugging completed January 17 1966  
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.  
If a producing well is abandoned, date of last production - - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation - - Depth to top - - Bottom - - Total Depth of Well 5055 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	386'	386'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - - feet to - - feet for each plug set.

Pushed plug to 380' with 1/4 sack hulls, cemented with 25 sacks cement, mud back to 40', set solid bridge, cemented with 15 sacks cement. Plug down 6:30 p.m. 1-17-66.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 24 1966

CONSERVATION DIVISION  
Wichita, Kansas

1-24-1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains ~~(owner or operator)~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of January, 1966.

My commission expires January 8, 1968

Shirley Keck  
Notary Public.

ROTARY DRILLING LOG

15-097-003-0000

Operator: Rains & Williamson Oil Co.  
 #1 Sloan  
 C SE SE Section 27-28S-20W  
 Kiowa County, Kansas

Contractor: Rains & Williamson  
 Oil Co.  
 Commenced: 1-3-66  
 Completed: 1-17-66

Remarks: Set 386' of 8-5/8" surface casing with 250 sacks GL3 cement.

FORMATIONS:

Surface Clay	335'
Sand	354'
Shale	500'
Anhydrite (Blaine)	515'
Shale	700'
Shale & Shells	1285'
Anhydrite	1318'
Shale & Red Bed	1685'
Shale	2150'
Shale & Lime	2225'
Lime & Shale	3980'
Lime	4025'
Lime & Shale	4215'
Lime	4275'
Lime & Shale	4485'
Lime	4525'
Lime & Shale	4655'
Lime	4683'
Lime & Shale	4791'
Lime	4842'
Lime & Shale	5055'
Rotary Total Depth (D&A)	5055'

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 24 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 21st day of January, 1966.

My Commission Expires:  
 January 8, 1968

*Shirley Keck*  
 Shirley Keck, Notary Public