

15-097-20508-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 24 Twp. 28S Rge. 20W E4W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____

C-NE NE
Lease Owner K R M Petroleum Corporation
Lease Name C. E. Sherer "C" Well No. 1
Office Address Guaranty Bank Bldg., 817 17th St., Denver,
Character of Well (Completed as Oil, Gas or Dry Hole) CO 80202
Dry Hole

Date Well completed January 11, 1979
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced January 11, 1979
Plugging completed January 11, 1979
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____
19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5,004'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	575'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 5,004 ft. (rotary total depth) to 540 ft. Set plug at 540 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 540 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~XXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 North Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 19 79

My commission expires July 25, 1982


Elsie Willdson Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1979

CONSERVATION DIVISION
Wichita, Kansas

1-23-1979



KANSAS DRILLERS LOG

COMPANY K R M Petroleum Corporation
FARM C. E. Sherer "C" NO. 1

SEC. 24 T. 28S R. 20W
LOC. C-NE NE

COUNTY Kiowa

ROTARY TOTAL DEPTH 5,004'
COMM. December 21, 1978 COMP. January 11, 1979
CONTRACTOR H-30, Inc. (Rig #77)
ISSUED January 22, 1979

CASING

10 3/4"
8 5/8" Set at 575' cemented w/400 sxs cement
5 1/2"
4 1/2"

ELEVATION 2,302' GR.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed, Shale and Shells	605'
Red Bed, Shale and Sand	1,135'
Red Bed, Anhydrite and Shale	1,789'
Lime and Shale	1,830'
Shale	3,093'
Shale and Lime	3,311'
Lime and Shale	3,497'
Shale and Lime	4,040'
Lime and Shale	4,595'
Lime	4,954'
Lime and Chert	5,004'
Rotary Total Depth	5,004'


I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas
County of Sedgwick

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 22nd day of
January, 1979.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1979
CONSERVATION DIVISION
Wichita, Kansas