

99

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Wichita Kans.

Operator's Full Name Shallow Water Repl. Co. 1325 Wichita Plaza

Complete Address: c/o P.O. Box 11320 - Kansas City Mo.

Lease Name Batholomew Unit Tract 16 Well No. 2

Location SF-SW-SF Sec. 31 Twp. 27 Rge. (E) 4 (W)

County Sedgewick Total Depth 3769

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight & Carver Plugging Co.

Address: Chapel Kansas License No. 436

Operation Completed: Hour 3:00 Day 21st Month 3 Year 1966

The Above well was plugged as follows:

Filled hole with sand to 3750 ft.
Mixed & dumped 5 sacks cement.
Pulled 3104 ft. of 7" casing -
Set a 15 ft. Rock Bridge at 215 ft.
Added 20 sacks of cement.
Mudded hole from this point to 20 ft.
Added 10 sacks of cement to surface.
(209 ft. of 10³/₄" surface Pipe - Circulated)

I hereby certify that the above well was plugged as herein stated.

Signed: Paul Gump
Well Plugging Supervisor

INVOICED

Paul Kaho

DATE 3-22-66

INV. NO. 4099-E