

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Imperial Oil Co.

Complete Address 720 4th. Financial Center, Wichita, Ks. 67202

Lease Name Repp Well No. 1-18

Location C SW NE Sec. 18 Twp 28s Rge. 15 (E) (WX)

County Pratt Total Depth 4695

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 2:30 Pm. Day 11 Month 4 Year 1980

The above well was plugged as follows:

365' 8 5/8" casing w/300 sax cement. 4 1/2" casing set at 4686' w/200
sax cement. Plug back to 4288'-Preforated at 4264' to 4268'-Sand back
to 4200'-Top sand w/4 sax mixed cement w/dump bailer. Pull 3840'
casing. Sun mixed & pumped 8 sax hulls-25 sax gel-125 sax 50/50 posmix
cement w/4% gel & 3% cc to top of casing. Shut in w/500# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1980

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 4/4/80
INV. NO. 1928w