

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name J. E. Newman

Complete Address: 2005 Tower Bldg., Denver, Colorado

Lease Name Rezeau Well No. # 1

Location NW NW SW Sec. 12 Twp. 28 Rge. 15 (E) (W) W

County Pratt Total Depth 4799

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Cherokee Drilling Co.

Address: 2005 Tower Bldg., Denver, Colorado License No. 350

Operation Completed: Hour 11:00AM Day 3rd Month June Year 1963

The Above well was plugged as follows:

268' of 8 5/8" surface pipe, cement circulated. 4550' of 2 1/2" tubing for
long string, cemented with 100 sacks. Top perforation 4476'. Hole was
squeezed to 3730' with 35 sacks cement by Halliburton Cementing Co.
Fluid level was up in hole, 3 sacks cement was mixed and set on plug,
through dump bailer, at 240' with 10' rock bridge, let set over night,
next morning hole bailed down, 17 sacks cement was added to plug. Hole
was filled with mud to 40', 10' rock bridge, cemented with 10 sacks to
base cellar. 2527' of 2 1/2" tubing, as long string was recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/11/63

INV. NO. 4231-4

Signed: Audie Elving
Well Plugging Supervisor