

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Imperial Oil Co.

Complete Address 720 4th. Financial Center, Wichita, Ks. 67202

Lease Name Jenkins Well No. 1-11

Location W/2 NE SE Sec. 11 Twp. 28S Rge. 15 (E) (W) W

County Pratt Total Depth 4650

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:15 Am. Day 7 Month 6 Year 1979

The above well was plugged as follows:

360' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 4530' w/225
sax cement. Plug back to 4100'. Preforated at 4060'. Sand back to 4000'.
Top sand w/4 sax mixed cement w/ dump bailer. Pull 3500' 4 1/2" casing.
Sun mixed & pumped 5 sax hulls-25 sax gel-release plug-mixed & pumped
125 sax cement w/4% gel & 3% cc To top of casing. Shut in w/200# pres.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 8 1979

I hereby certify that the above well was plugged as herein stated ^{CONSERVATION DIVISION} _{Wichita, Kansas}

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6-11-79
INV. NO. 9984-W