

15-159-30362-0000

Form CP-3
Rev. 6-4-68

KANSAS

20
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1972
10-10-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company, Inc.

Complete Address 200 W. Douglas, Wichita, Kansas 67202

Lease Name Blackhall Well No. 2

Location SE SE SE Sec. 5 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3769'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 3:00 PM Day 6 Month October Year 1972

The above well was plugged as follows:

5 1/2" plug pushed to 3590'. Hole filled with sand to 3575' and hole cemented with 5
sacks cement. Hole bailed to 205'. Rock bridge set from 205' to 195' and hole
cemented with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from
40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *J. Lewis Brock*
Well Plugging Supervisor

DATE 10/11/72
INV. NO. 6436-W