

15-159-30312-0000

Form CP-3
Rev. 6-4-68

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Inc.

Complete Address 200 W. Douglas, Wichita, Kansas 67202

Lease Name Blackhall Well No. 3

Location SW SE SE Sec. 5 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3550'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 10 AM Day 9 Month August Year 1971

The above well was plugged as follows:

Pushed 7" plug to 3415'. Filled hole with sand to 3400' and cemented hole with 6
sacks cement. Set rock bridge from 203' to 195'. Dumped 5 sacks cement on bridge
and left to set over night. Hole bailed dry and cemented with 20 sacks (total 25
sacks). Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole
cemented to base of cellar with 15 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8-18-71
INV. NO. 4182-W