

15-159-30311-0000  
Form CP-3  
Rev. 6-4-68

KANSAS

*SL*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Inc.

Complete Address 800-200 W. Douglas, Wichita, Kansas 67202

Lease Name Timbers Well No. 1

Location App. NW NE NE Sec. 8 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3623'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 9:30 AM Day 16 Month July Year 1970

The above well was plugged as follows:

5 1/2" plug pushed to 3310'. Hole filled with sand to 3300' and cemented with 5 sacks  
cement. Hole bailed to 210'. Rock bridge set from 210' to 200' and hole cemented  
with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30'  
and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/17/70

INV. NO. 2242-U

Signed: *Arthur J. Loman*  
Well Plugging Supervisor