

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed August 16, 1967.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 4 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Wrico Drilling Company

Complete Address: 6631 East Kellogg, Wichita, Kansas

Lease Name Pagett Well No. # 1

Location SE NE SW Sec. 20 Twp. 27 Rge. 5 (E) (W) W

County Kingman Total Depth 3835'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: H-30 Drilling, Inc.

Address: 200 North Main, Wichita, Kansas License No.     

Operation Completed: Hour 5:00PM Day 1st Month Oct. Year 1967

The Above well was plugged as follows:

209' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole  
was filled with drilling mud to 200', 1st cementing plug, bridged with  
2 sack of dry cement and 1/2 sack of hulls on fluid at 200', and cemented  
with 23 sacks, with cement from 190' to 115'. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement  
and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks, with  
cement from 30' to the base of the cellar. Rat hole bridged and cemented  
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 10/4/67

INV. NO. 6449-4