

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Grest Petroleum Inc.

Complete Address 6631 E Kellogg Wichita, Ks

Lease Name Zerger Well No. 2

Location C NW/NE Sec. 31 Twp. 27 Rge. 5 (E) (W) W

County Kingman Total Depth 3796

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Shephard Drlg. Co.

Address 320 McCabe Winfield, Ks License No. 563

Operation Completed: Hour 2:00 PM Day 5 Month 10 Year 1972

The above well was plugged as follows:

210 ft 8 5/8 surface pipe cement circulated. 3790 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 3382 ft. Sand to 3350 ft. 5 sacks
cement with bailer. Pulled 2800 ft 5 1/2. Set 10 ft rock bridge at
165 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/11/72

INV. NO. 6449-W