

15097-10706-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name William Gruenerwald & Associates Inc

Complete Address Box 909 Colorado Springs, CO

Lease Name Price Well No. 2

Location G NW/NE Sec. 4 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5025

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sergents Casing Pulling Co Inc

Address 620 S Lincoln Liberal, KS License No. 511

Operation Completed: Hour 11:00 PM Day 27 Month 8 Year 1975

The above well was plugged as follows:

570 ft 8 5/8 surface cement circulated. 5024 ft 4 1/2 long string
cemented with 150 sacks. Top perf. 4919. Pump 2 hulls, 15 sacks
cement to 4700 ft. Pulled 1866 ft 4 1/2. Pump 2 sacks hulls, 15 sacks
gel, 35 sacks cement to 470 ft. Mud to 40 ft, plug, 15 sacks cement
to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9/3/75

INV. NO. 1847-W