

15-097-30016-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Wm. Gruenerwald & Associates, Inc.

Complete Address: Box 909, Colorado Springs, Colorado.

Lease Name J. W. Price Well No. # 1

Location C SE SE Sec. 4 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 2:00 AM Day 13th Month June Year 1965

The Above well was plugged as follows:

499' of 8 5/8" surface pipe, cement circulated with 400 sacks. Hole was
filled with drilling mud to 280', 1st cementing plug, bridged solid with
dry cement and hulls on fluid at 280', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cenment and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cementwd with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/14/65

INV. NO. 1305-W