

KANSAS
STATE CORPORATION COMMISSION

R

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-05700074-0000

File No. 135-28 County: Ford

Location: SW SW SE Sec. 14 Twp. 28 Rge. 21 (E) (W) X

Name of Field: P Total Depth: 5145

I have this date completed supervision of plugging of:

Lease Name: Vice Well No. 1

Operator's Full Name: Petroleum Management Inc.

Complete Address: 1019 Central Bldg Wichita Kansas

Plugging Contractor: South West Paving & Drilling Co Inc.

Address: West Bend Kansas License No. _____

Oil Well _____ Gas Well P Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: Very Poor Cooperation from

Plugging Contractor. Made six trips to Well. Drove 1044 mi

Did not call when completed.

Operation Completed: Hour P Day P Month P Year 58

The above well was plugged as follows:

Instructions were 13 7/8" 422' C.W.C. 5 1/2" 5135' P.B. 5050' Tot

Prof 5038' hole filled with sand to 3080' dump 3-4

cu. ft. set Ball 3/4 to about 1200' lic with Jell Mud.

Pull 5 1/2" Check Mud to 420' set Rock fidge dump 30 1/4

Cement. Mud to 20' set Rock fidge cement to face

of collar 10 1/4

Jell Mud was pumped by sun ascending to

on 10-26-58. 60 sv. but not circulated.

Signed: M. L. Rice
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 14 T. 28 R. 21W
BOOK PAGE 135 LINE 28

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1958

CONSERVATION DIVISION
KANSAS

11-12-58

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-057-00074-0000

CITY PRODUCTS CORPORATION &

Company: W. J. COPPINGER
Farm: Vice No. 1

SEC. 14 T. 28 R. 21W
SW SW NE

Total Depth: 5230
Comm: 1-11-54 Comp. 2-10-54
Shot or Traced:
Contractor: W. J. Coppinger
Issued: 3-27-54

County: Ford
KANSAS



CASING:

13 3/8 @ 422' w/ 400 sx cmt.
5 1/2 @ 5135' w/ 125 sx cmt.

Elevation: 2397 RB
Production: 7,685,000 Gas

Figures in Dots Bottom of Formations

sand	70
water & gravel	115
clay	140
sand	170
shale	340
sand	360
shale	430
red bed & shale	570
sand	585
gravel	630
red bed & shells	910
red bed & shale	1100
red bed & shells	1375
lime & anhydrite	1408
red bed, shale & shells	1620
shale & shells	2390
shale & lime	2615
lime	2665
lime & shale	3850
lime	3960
lime & shale	4015
lime	4175
lime & shale	4360
lime w/ thin shale streaks	4954
lime	4984
chert & shale	5022
lime w/ some chert	5230
Total Depth	

TOPS: Sample

Topeka	3696
Lansing	4360
Mississippi lime	5022

REGISTERED
STATE CORPORATION COMMISSION

DEC 4 - 1958

PLUGGING
FILE SEC 14 T 28 R 21W
BOOK PAGE 135 LINE 22

CONSERVATION DIVISION
Wichita, Kansas