

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-067-20,182-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Pickwell Drilling Co.

Complete Address Litwin Bldg. Suite 205 Wichita, Kansas 67202

Lease Name Hicks Well No. A-2

Location C-5 1/2 - N 1/2 Sec. 11 Twp. 28S Rge. 21W (East)(West)

County Gord Total Depth 5105'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was completed but not produced

Plugging Contractor Nelson Casing Pulling

Address Box 176 Chase Kansas License No. 681

Operation Completed: Hour: 1:00 PM. Day: 13 Month: January Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

*There is 611' of 8 1/8" surface casing cement circulated with 295 lbs of cement
They ran 5070' of 4 1/2" production pipe cemented it with 150 lbs with
cement up out side of pipe to 4410'. The perforations are at 4953' to
63' above plug back to 4965'. 1st plug sand bottom back
to 4900' with 4 sbp of cement on top of sand. 2nd plug 5 sbp
hulls 17 sbp Jell 50 cement 8 sbp Jell release rubber plug and
then pump in 100 sbp cement. Cement used was 50/150
grain with 4% Jell & 3% C.C. They recovered 4020' of 4 1/2" prod
pipe. The plugging was accomplished by all cementing.*

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

RECEIVED STATE CORPORATION COMMISSION
Signed: Paul L. Smith
Conservation Division Agent

2-9-82
INV. NO. 9342-W

JAN 19 1983
CONSERVATION DIVISION
Wichita, Kansas 1-19-83

105.01