

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-857-60094-0000

FILE NO. 68-5

LOCATION CNE-SW

SEC. 1 TWP. 28 RGE. 21-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Maesha Estate

Operator Republic Natural Gas Co. Address Box 98 - Hugoton - Kans -

Field \_\_\_\_\_ County Ford

Total Depth 4005 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 443 ft. Circulated with cement.  
7' casing set at 500 ft. Cemented with 175 sacks cement.  
Plugged back to 4200 ft with sand-lime Wall Plug  
& shot - Dumped 6 sacks of cement at 4200 ft - shot off  
& pulled the 7' casing - mud to 250 ft. Set Rock  
Bridge & 20 sacks of cement at 250 ft - mud to 30 ft -  
Plug & 10 sacks of cement at the surface -  
Well Supply Co. Plugging Contractor

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1951

4-18-51  
C. W. Stough  
District Conservation Agent

PLUGGING  
FILE SEC 1 TWP 28 RGE 21  
BOOK PAGE 68 LINE 5

Date 4-16-51