

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-097-30031-0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Ralstin Well No. # 1

Location C SW NE Sec. 36 Twp. 28 Rge. 20 (E) (W)

County Kiowa Total Depth 5038'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drilling Company

Address: 1720 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 7:30PM Day 22nd Month August Year 1965

The Above well was plugged as follows:

628' of 8 5/8" surface pipe, cement circulated with 325 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug bridged solid
with hulls on fluid at 300', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/30/65

INV. NO. 1720-W