

KANSAS
STATE CORPORATION COMMISSION

15-097-10093-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1963

2-19-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jones and Gebert Oil Co.

Complete Address: 1007 Central Bldg., Wichita 2, Kansas

Lease Name Sidener Well No. # 1

Location C NE SE Sec. 30 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5185

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Jones and Gebert Oil Co.

Address: 1007 Central Bldg., Wichita 2 Kansas License No. _____

Operation Completed: Hour 5:00AM Day 15th Month Feb. Year 1963

The Above well was plugged as follows:

405' of 8 5/8" surface pipe circulated with cement. Hole was filled
to 180' with heavy mud, 1/2 sack hulls, 1st cementing plug, cemented
with 20 sacks. Hole was filled to 40' with mud, 1/2 sack hulls, 2nd
cementing plug, cemented with 10 sacks to the base of cellar. Rat
and mouse hole was bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/19/63
INV. NO. 6606-W

Signed: Audie Elving
Well Plugging Supervisor