

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed January 12, 1968.

15-097-20042-0000

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name _____ Price _____ Well No. _____ # 1

Location C SE NW Sec. 27 Twp. 28 Rge. 20 (E) (W) W

County Kiowa Total Depth 5028'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Rains & Williamson Oil Company, Inc.

Address: 1425 Wichita Plaza Bldg., Wichita, Ks. 67202 License No. _____

Operation Completed: Hour 2:30AM Day 26th Month January Year 1968

The Above well was plugged as follows:

494' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level in the hole was 290'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 300', and cemented with 25 sacks, through the drill pipe, with cement from 300' to 225'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 1/29/68

INV NO 7160-4