


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

15-159-30311-0000

Form CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Rice County. Sec. 8 Twp. 21 Rge. 8 (E) (W)
Location as "NE/CNW/SE" or footage from lines NW NE NE
Lease Owner Raymond Oil Co., Inc.
Lease Name Timbers #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7/10/70 19
Plugging completed 7/16/70 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3623' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	214	none
				5 1/2	3613	2800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3571', pushed plug to 3310' and ran sand to 3300', ran 5 sacks of cement. Shot pipe at 2898', 2802', spotted 40 barrels oil and 70 water with 500 lb. pressure. Worked pipe loose and pulled 88 joints. Bailed hole to 210', set 10' rock bridge and ran 25 sacks of cement. Mudded hole to 40', set 10' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of July, 19 70

My commission expires 2/15/71

Margaret D. Welch
Notary Public.

RAYMOND OIL COMPANY, INC.
 #1 TIMBERS
 90' East NW NE NE Sec. 8-21S-8W
 Rice County, Kansas

ELEVATION: 1657 KB
 1655 DF
 1652 GL

Drilling Contractor: Company Tools
 Date Commenced: December 10, 1966
 Date Completed: December 19, 1966

Casing Record
 8-5/8" @ 214' w/240 sx.
 5-1/2" @ 3613' w/150 sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Top Soil	80
Sand	85
Red Bed & Shale	208
Anhydrite	220
Shale	238
Shale & Shells	1030
Shale & Lime	1167
Lime & Shale	1940
Shale w/Lime Streaks	2151
Lime & Shale	2717
Heebner	2722
Lime	2724
Lime & Shale	2948
Lime	3183
Conglomerate	3234
Kinderhook	3240
Lime, Chert, Shale & Sand	3285
Misener Limestone	3285
Sand & Lime	3324
Viola	3355
Lime & Chert	3376
Simpson	3400
Shale, Lime & Sand	3438
Sand & Lime	3446
Arbuckle Shale	3450
Arbuckle	3623
RTD	3623

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 30 1970
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Wm. M. Raymond
 Wm. M. Raymond

Subscribed and sworn to before me this 27th day of December, 1966.

Ronnie Donnelly
 Ronnie Donnelly - Notary Public

My commission expires:
 February 15, 1967

