

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151,20,683-00-01

LEASE NAME Whitney

WELL NUMBER #2

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 31 TWP. 28 RGE. 15 (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 12-15-86

Plugging Completed 1-8-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sharp Engineering Oil Operation

ADDRESS One Main Place Suite 708, Wichita, Ks. 67202

PHONE # (316) 788-3365 OPERATORS LICENSE NO. 9427

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4917'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
					8-5/8"	None
					4-1/2"	2,351.44'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 4595' and 4 sacks cement. Shot casing at 3750', 3550', 3000', 2500' and 2000'. Pulled 60 joints of 4-1/2" casing. Halliburton squeezed well with 3 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, and 120 sacks 60/40 pozmix with 6% added gel.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1987

My Commission Expires _____



Iona M. Leatherman
Notary Public
STATE CORPORATION COMMISSION

JAN 14 1987
01-14-87
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 07-86

DRILLERS LOG

No. 1-31 Whitney

ASING RECORD: COMPANY: Imperial Oil Company DESCRIPTION:
 5/8" @ 365' CONTRACTOR: Red Tiger Drilling Company C SW/4 SW/4
 /275 sx cement COMMENCED: October 18, 1979 Sec. 31-T28S-R15W
 Pratt County, Kansas
 COMPLETED: October 29, 1979

TOTAL DEPTH: 4,917' ELEVATION: 2,083' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
and & Red Bed	0	370	
and	370	550	
and & Shale	550	988	
hydrite	988	1008	
ale	1008	1730	
ale & Lime	1730	2520	
ime	2520	3285	
ime & Shale	3285	3935	
ime	3935	4917	
D		4917	


certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
 Gloria Fawcett

scribed and sworn to before me this 31st day of October, 1979.

Joyce A. Hagermann
 Notary Public



REPORTS FOR
WASHDOWNS or OWWO

DEC 15 1982

APJ 15-151-20683 A

OPERATOR Imperial oil Co
 LEASE WHITNEY
 WELL NO. 1-31
 SPOT LOCATION C SW SW 31-28-15 660 FSL 660 F02
 COUNTY Pratt
 CONTRACTOR Pratt well Service
 DATE & TIME SCHEDULED 10:00 am 6 Dec 1982
 RIG # Double Boom LICENSE # 5021 Tag 447

Were samples of plugs drilled collected? yes no

Plugging report is attached. pluggs
 600' 40 SY
 360' 40 SY
 40' - 12 SY

PLUGS FOUND FROM	---	TO	DRILLING TIME
0		40'	Hard Cement 3 min per Foot
330'		435'	Hard Cement 2 min per Foot
435'		592	Soft Cement 1 min per Foot

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 20 1982
 CONSERVATION DIVISION
 Wichita, Kansas

metz by
 KC