

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151,21,431-0000

LEASE NAME Whitney

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER "A" #1

660 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 31 TWP. 28 RGE. 15 (E) or (W)

COUNTY Pratt

LEASE OPERATOR Sharp Engineering Oil Operations

ADDRESS One Main Place, Suite 708, Wichita, Ks. 67202

PHONE # (316) 788-3365 OPERATORS LICENSE NO. 9427

Date Well Completed _____

Character of Well Oil

Plugging Commenced 12-22-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-8-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4729'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	356'	None
				4-1/2"	4729'	2,703.88'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped sand to 4600' and 4 sacks cement. Shot casing at 3800', 3000' and 2700'. Pulled 66 joints of 4-1/2" casing. Halliburton squeezed well with 3 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls and 120 sacks 60/40 pozmix cement.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) James W. Rockhold

(Address) James W. Rockhold
 Box 698, Gr. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 13th day of January, 1987

Iona M. Leatherman
 Notary Public

My Commission Expires:



STATE CORPORATION COMMISSION

01-14-87 JAN 14 1987 Form CP-4
 Revised 07-86
 CONSERVATION DIVISION
 Wichita, Kansas