

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,633A

LEASE NAME Smith (OWWO)

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 30 TWP. 28S RGE. 15 ~~K&K~~ (W)

COUNTY Pratt

Date Well Completed 6-21-89

Plugging Commenced 6-21-89

Plugging Completed 6-22-89

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-22-89 (date)

by State Plugger, Dick Kapp (KCC District Agent's Name).

Is ACO-1 filled? yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 1100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	309' on	None
					old well	

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Circulate heavy mud in hole. 1st plug from 1100' to 900' w/50 sx. 2nd plug from 380' to 220' w/40 sx. 3rd plug from 40' to surface. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

Unable to penetrate beyond 1100' - Hole was abandoned.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jerry A. Langrehr (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Jerry A. Langrehr

(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 26th day of July, 1989

Sharan J. Branstetter Notary Public
My Commission Expires: May 18, 1993

