

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.151.21285-00.00

LEASE NAME Poovey

WELL NUMBER 1

SPOT LOCATION NW NW NW

SEC. 28 TWP 28S RGE. 15 (E) or (W)

COUNTY Pratt

Date Well Completed 11-6-83

Plugging Commenced 11-29-85

Plugging Completed 11-30-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ainsworth Drilling Co.

ADDRESS Box 1269 Colorado Springs, CO 80901

PHONE # (303) 576-5300 OPERATORS LICENSE NO. 6030

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Marmiton Depth to top \_\_\_\_\_ bottom T.D. 4864'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0		8 5/8		0
				5 1/2		55 jts. + 2 short jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
11-29-85 Dumped 65 gal. sand-70 feet of fillup. dumped 5 sx. cement, tried to pull casing loose.


11-30-85 Mercury Wire Line shot off casing--pulled 55 jts and 2 jts. (short) of 5 1/2.  
12-3-85 Halliburton top hole plugging. 300# hulls-15 sx.gel-50 sx.cement-10 sx.gel-100# hulls-pumped 115 sx. cement with 1 bbl. fresh water. 400# ISIP, job complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service License No. 5893  
Address Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (employee of operator) or  
(XXXXXXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry  
(Address) Box 847 Pratt, Kansas



SUBSCRIBED AND SWORN TO before me this 17 day of December, 1985

My Commission expires: February 6, 1989

Dorothy M. Ferguson  
STATE CORPORATION COMMISSION