


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 20 Twp. 27S Rge. (E) 5 (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner Shawver-Armour, Inc. et al  
Lease Name Handkins Well No. 1  
Office Address 817 Central Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 10-15 19 58  
Application for plugging filed 10-15 19 58  
Application for plugging approved 10-15 19 58  
Plugging commenced 10-15 19 58  
Plugging completed 10-15 19 58  
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gene Graham  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4228 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	193'	8 5/8"	193'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Went to T. D. goned up pits bring heavy mud around.  
Layed down pipe Heavy mud to 200'  
# 1 Plug Howeo Plug 1/4 sk Hulls 20 sk. cement thru drill pipe  
Heavy mud to 40'  
# 2 Plug Howeo Plug 1/4 sk. hulls 10 sk cement to base of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.  
Address 817 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
JAMES M. ARMOUR (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour  
JAMES M. ARMOUR  
817 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of October, 1958

My commission expires July 19, 1960  
Michael Ludemann Notary Public.

PLUGGING  
FILE SEC 20 T. 27. R. 5W  
BOOK PAGE 139 LINE   

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 25 1958  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOG

FARM NAME: HANDKINS # 1 LOCATION: NW NW SE Sec. 20-27S-5W  
 COMPANY: SHAWVER-ARMOUR, INC. KINGMAN COUNTY, KANSAS  
 COMMENCED: 9-29-58 COMPLETED: 10-15-58  
 CASING RECORD: 193' 8 5/8" W/165 sx. 2% cc ELEVATION: 1484 K.B.

DEPTH:

TOPS:

Sandy Loam	7		
Sand & Clay	38	Brown Lime	2971
Red Bed & Greenish Shale	160	Lansing Kansas City	3003
Hard Red Bed & gray-greenish Rock	193	Base Kansas City	3437
Red Bed & Sand Rock	300	Mississippi	3758
Shale	535	Kinderhook	4038
Salt & Shale	765	Viola	4156
Anhydrite & thin Shale Streaks	930	Simpson	4178
Anhydrite & Shale Streaks	1130		
Lime & Shale	1225		
Shale	1250		
Lime	1275		
Lime & Shale	1580		
Lime	1600		
Lime & Shale	1670		
Shale & Lime Streaks	2000		
Shale & Lime	2260		
Lime & Shale	2285		
Shale & Lime	2380		
Lime & Shale	2416		
Shale & Lime	2828		
Shale & Shells	2980		
Lime & Shale	3003		
Kansas City Lime	3415		
Lime & Shale	3620		
Shale & Lime	3715		
Mississippi Chert	3768		
Chert & Lime	3826		
Mississippi Chert & Shale	3868		
Mississippi Lime	3950		
Lime & Shale	3984		
Mississippi Lime	4023		
Lime & Shale	4062		
Shale & Lime	4159		
Viola Lime	4172		
Simpson Sand	4179		
Lime & Shale	4188		
Simpson Sand and Shale	4225		
Simpson	4228	T D	D & A

STATE OF KANSAS)  
 )SS  
 SEDGWICK COUNTY)

I, James M. Armour, do hereby certify that the above is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

BY James M. Armour  
 JAMES M. ARMOUR

Subscribed and sworn to before me this  
27 day of October, 1958

My commission expires: July 19, 1960

Melvin L. Linn  
 Notary Public

PLUGGING  
 FILE SEC. 20 T 27 R 5W  
 BOOK PAGE 139 LINE 6

**RECEIVED**  
 STATE CORPORATION COMMISSION

OCT 25 1958

CONSERVATION DIVISION  
 Wichita, Kansas