


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County, Sec. 31 Twp 27S Rge. (E) 5 (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Crest Petroleum, Inc.
Lease Name Zerger Well No. 3
Office Address 6631 E. Kellogg, Wichita, Kansas 67207
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 10 19 70
Application for plugging filed Verbal Request 19
Application for plugging approved Verbal Authority
Plugging commenced May 10 19 70
Plugging completed May 10 19 70
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	209'	None

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,185 feet (rotary total depth) to 480 feet. Set bottom plug at 480 feet and cemented with 40 sacks cement. Filled hole with heavy rotary mud to 200 feet. Set plug at 200 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented to cellar with 12 sacks cement, 3 sacks cement in rathole. Cementing done by Halliburton Pump Truck.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, INC.
Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main, Wichita, Kansas 67202
(Address)

Subscribed and Sworn to before me this 12th day of May, 1970

My commission expires April 21, 1971
Martha Hartpence
Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Crest Petroleum, Inc.

SEC. 31 T. 27S R. 5W
 LOC. C SW NE


FARM Zerger NO. 3

TOTAL DEPTH 4,185'
 COMM. April 28, 1970
 SHOT OR TREATED
 CONTRACTOR H-30, INC.
 ISSUED

COMP. May 10, 1970

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 14 1970
 CONSERVATION DIVISION
 Wichita, Kansas

COUNTY Kingman
 KANSAS



CASING

20	10	
15	5 1/8"	209' cemented w/200 sacks cement
12	6	
13	5	

ELEVATION 1443 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Shale	415	<u>SAMPLE TOPS:</u>	
Shale & Lime	1170	Topeka	2333- 890
Shale, Lime & Shells	1379	Heebner	2704-1261
Shale & Lime	2010	Toronto Lime	2719-1276
Lime & Shale	2799	Douglas Shale	2734-1291
Shale & Lime	2974	Brown Lime	2931-1488
Lime	3590	Lansing	2963-1520
Lime & Shale	3745	Base K.C.	3459-2016
Lime & Chert	3787	Marmaton Lime	3491-2048
Lime	3792	Cherokee Shale	3637-2194
Chert	3805	Mississippi	
Chert & Lime	3880	Chert	3743-2300
Lime & Chert	3909	Mississippi	
Lime	4079	Dolomite	3784-2341
Lime & Shale	4108	Kinderhook	
Lime	4165	Shale	4036-2593
Sand	4171	Misener Sand	4103-2660
Lime	4178	Viola Sand	4139-2696
Sand	4185	Simpson Sand	4165-2722
Rotary Total Depth	4185	Rotary T.D.	4185-2742

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 12th day of May, 1970.

Martha Hartpence

 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971