

15-097-20884-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 4 TWP. 28s RGE. 20w E/W
 Location as in quarters or footage from lines:
NW NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Southwind Petroleum Corp.
 Lease Name Price Seimons #1 Well No. _____
 Office Address 1825 West 13th St. Wichita, Ks. 67203
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 4/26/83
 Plugging completed 4/29/83
 Reason for abandonment of well or producing formation _____

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom T.D. 4921'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	635'	none
				4 1/2"	4920 1/2'	3218'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged obttom hole back with sand to 4850' & ran 4 sacks cement. Shot casing at 4045', 3630', & 3220'. Pulled total of 80 joints. Squeezed hole with 3 hulls, 15 gel, 70 cement, 10 gel, 1 hull. Released plug & displaced with 175 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347, Chase, ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 83




Irene Hoover
 Notary Public.

My Commission expires: _____

RECEIVED
 STATE CORPORATION COMMISSION

MAY 06 1983

CONSERVATION DIVISION
 Wichita, Kansas



WHITE

ANDELLISDRILLING, Inc.

15-097-20884-0000

DRILLERS LOG

OPERATOR: Southwind Petroleum Corp. 1825 W. 13th St. Wichita, Ks. 67203

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Price-Seimens Well No. #1

Sec. 4 T. 28S R. 20W Spot NW NE

County Kiowa State Kansas Elevation GL 2305'

Casing Record:

Surface: 8 5/8" @ 635' with 375 sx. 3%cc
Production: 4 1/2" @ 4920 1/2' with 150 sx. 2%gel

Type Well: Oil Total Depth 4921'

Drilling Commenced 6-23-82 Drilling Completed 7-4-82

Formation	From	To	Tops
Cellar	0	7	
Sand, Shale	7	1052	
Shale, Lime	1052	2330	
Lime	2330	2770	
Lime, Shale	2770	2925	
Lime	2925	3080	
Shale, Lime	3080	3295	
Lime	3295	3444	
Lime, Shale	3444	4595	
Lime ..	4595	4921	