

15-197-30016-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County. Sec. 4 Twp. 28S Rge. (E) 20W(W)  
Location as "NE/CNW/SW" or footage from lines SE/4 SE/4  
Lease Owner Wm. Gruenerwald & Assoc., Inc.  
Lease Name J. W. Price Well No. 1  
Office Address Box 909 Colorado Springs, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 13 1965  
Application for plugging filed June 12 1965  
Application for plugging approved June 12 1965  
Plugging commenced June 12 1965  
Plugging completed June 13 1965  
Reason for abandonment of well or producing formation No producible shows

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5050 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	499'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 280', 2 sacks of dry cement on top of fluid, 1/3 sack of hulls, 23 sacks of cement through surface casing. Heavy mud to 40', 1 sack of dry cement plug to 40', 9 sacks of cement to bottom of cellar. Placed 3 sacks of cement in rat hole. Job complete 2 AM, 6-13-65.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 27 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address RR #2 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
A. G. Radke (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. G. Radke

Garvey Drilling Co. RR #2, Great Bend,  
(Address) Kansas

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1965

My commission expires April 14th, 1967

Arthur J. [Signature]  
Notary Public.

WELL LOG

15-097-30016-0000

COMPANY **Wm Gruenerwald & Assoc., Inc.**

SEC. 4 T. 28S R. 20W

FARM **J. W. Price**

NO. 1

LOC. SE SE


TOTAL DEPTH **5050'**

COUNTY **Kiowa, Kansas**

COMM. **5-28-65**

COMP. **6-13-65**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 499' w/400 sx**

ELEVATION **2315' DF**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 195' Sand
- 285' Shale
- 499' Shale, Shells, and Red Bed
- 630' Shale and Shells
- 740' Red Bed
- 765' Anhydrite
- 1094' Shale and Shells
- 1550' Red Bed, Shale, Gyp and Salt
- 1906' Shale and Lime Streaks
- 2340' Shale and Lime
- 2460' Lime and Shale
- 2670' Lime
- 2975' Lime and Shale
- 3264' Shale and Lime
- 3430' Lime and Shale
- 4108' Shale and Lime
- 4284' Lime and Shale
- 4294' Brown Lime
- 4360' Lansing Lime
- 5050' Mississippi Lime
- 5050' RTD

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 27 1965  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company  
J. W. Price #1

upon oath state the above and foregoing is a true and correct copy of the log of the \_\_\_\_\_ well.

Subscribed and sworn to before me this 19th day of June 1965

My Commission Expires: May 28, 1969  
Richard H. Dumbler  
NOTARY PUBLIC

